BRUHATH BANGALORE MAHANAGARA PALIKE

YELAHANKA ZONE

Name of Work : Improvements of compound wall in Byatarayanapura SC'S Burial Ground In ward no 07 Byatarayanapura

Estimate cost Rs. 1500000.00

Sl. No.	Description of Item	Unit	No.	L	B	D	Qty.	Rate	Amount
1	KSRRB 300-1. Earth work excavation by manual means in hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications MORTH chapter 3. No. 138 Item No. 19.2/ PWD SR 2014-15.								
	Drain		1	60.00	1.00	1.00	60.00		
	For Compound Wall		1	19.00	0.90	1.00	17.10		
	For Sanitary Line		1	100.00	0.60	0.75	45.00		
							122.10	105.84	12923.00
	Basic Rate	98.00							
	Area Weightage @ 8%	7.84							
	Total	105.84							
2	Providing and laying reinforced cement concrete pipe NP3 for culverts including pointing ends, and fixing collars with cement mortar 1:2 including cost of all materials, labour, curing complete as per spefications. Specification No. 1000/2300 MOST Specifiaction no. 1000/2300 **450mm dia (Page no. 244 Item no. 34.62) PWD 2014-15**							m	
			1	60.00			60.00	2958.12	177487.00
	Basic Rate	2739.00							
	Area Weightage @ 8%	219.12							
	Total	2958.12							
3	KSRB 12-8.3 : Constructing brick masonry inspection chamber 600x850mm, and 450mm depth, (clear inside dimension) for pipeline with three or more inlets, using table moulded non-modular bricks of class designation 50 in cement mortar 1:5m C.I cover with frame (light duty) 455x610mm internal dimensions, total weight of cover with frame (light duty) 455x610mm internal dimensions, total weight of cover with frame to be not less than 38kg (weight of cover 23kg and weight of frame 15kg) R.C.C top slab with cement concrete M 15 with 20mm and downsize granite metal, foundation concrete M5 with 40mm and downsize granite metal inside plastering 12mm thick with cement mortar 1:3 finished smooth with a floating coat of cement on walls and bed concrete complete as per standard design including cost of materials, labour charges, curing complete as per specifications. specification no. KBS (P no. 71 Item no. 11.54)PWD 2014-15						Each		
	Sanitry			8			8.00	8672.40	69379.00
	Basic Rate	8030.00							
	Area Weightage @ 8%	642.40							
	Total	8672.40							
4	KSRB 2.3: Filling available excavated earth (excluding rock) in sides of foundations upto plinth in layers not exceeding 20cms. In depth, compacting each deposited layer by ramming after watering with lead upto 50m and lift upto 1.5m including cost of all labour complete as per specifications. specifications no. KBS 2.9 (Page no. 6 Item no. 2.10)								
			vide item no. 1				60.00	118.80	7128.00
	Basic Rate	110.00							
	Area Weightage @ 8%	8.80							
	Total	118.80							
5	KSRB 5-14 Providing and constructing precast concreate solid blocks with compressive strenth not less than 3.5 new ton sq mm with cement mortor 1:4 masonary (quioin , jamb closer blocks) with solid concrete blocks of size 40X20X20cms conforming conforming to i.s : 2185/1965 in superstructure including cost of materials labour charges scaffolding curing complete as per specification . KBS 5-14 (Page no. 25 Item no. 5.27)								
	Buriol Ground compound	Sqm	1	53.00		0.75	39.75		
			1	18.00		2.50	45.00		
			1	88.00		0.75	66.00		
							150.75	993.60	149785.00
	Basic Rate	920.00							
	Area Weightage @ 8%	73.60							
	Total	993.60							

6	KSRB 5.3-3 : Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. (P.No.23 I.No.5.9of PW,P&IWTD S.R 2014-15							Cum	
			2	18.00	0.60	0.60	**12.96**		
			1	19.00	0.70	0.60	**7.98**		
			1	19.00	0.45	0.45	**3.85**		
							24.79	**4458.36**	**110512.00**
	Basic Rate Rs.	4206.00							
	Add 6% A.W Rs.	252.36							
	Total Rate Rs.	**4458.36**							
7	KSRB 4-1.5 Providing and laying position plain cement concreate of mix m20 with opc cement @ 300kgs with 20mm down size grade granite metal course aggregates @0.69 cum and fine aggregates @ .43 cum with super plastier @3lts confirming to IS9103-1999 Reffirmed 2008 machine mixed concrete layers not exeeding 15 cms thick well compacted in foundation plinth and cills including cost of all materials labour HOM of machinery curing as per specification KBS 4.1,4.2 (Page no. 12 Item no. 4.5								
	Buriol Ground compound	Sqm	**1**	**53.00**	**0.30**	**0.10**	**1.59**		
			1	**18.00**	**0.30**	**0.10**	**0.54**		
			1	**88.00**	**0.30**	**0.10**	**2.64**		
			1	**19.00**	**0.45**	**0.10**	**0.86**		
			1	**19.00**	**0.60**	**0.10**	**1.14**		
							6.77	**5852.52**	**39592.00**
	Basic Rate	5419.00							
	Area Weightage @ 8%	433.52							
	Total	5852.52							
8	KSRB 6-8.2 Construction of partition wall 10cms thick with table moulded Modular burnt bricks of class designation 5.0 newtown per sqmm with cement mortor 1:4 including providing and fixing plster mesh manufactured out of hot dippedc gelvanced iron of nominal thickness 0.35 mm 100mm wide as per I.S 2212/1991 at 7.5 m.c to c including cost of materials labour charges , scaffolding , curing complete as per specification : No KBS 6.2 . pG NO : 29 item no : 6.28)								
	Compound Wall		1	15.00	1.50		22.5		
			1	10.00	0.9		9.00		
							31.50	**783.00**	**24665.00**
	Basic Rate	725.00							
	Area Weightage @ 8%	58.00							
	Total	783.00							
9	KSRRB 15-3.10 Providing 20mm thick cement plaster in single coat mortor 1:3 to ceiling including ronding off corners wherever required smooth rendering providing and removing scaffolding including cost of materials laboures , curing complete as per specifications Pg no 110 Itemno : 15.18								
			2	15.00	1.50		45.00		
			1	10.00	0.90		9.00		
							54.00	**253.80**	**13705.00**
	Basic Rate	235.00							
	Area Weightage @ 8%	18.80							
	Total	253.80							
10	13.9.1 Providing and fixing to wall , ceiling and floor high density polythelene pipes 6.00kgs /sqcm working pressure 32mm outside diameter raising mains & exposed distrubition pipes with special flange compression type fitting , wall clips making good the wall , ceiling and floor including cost of all materials labour charges HOM of equipments and testing complete as per specification KSRB 13-8.9 -do- 140mm . Pg no : 91								
			2	**150.00**			**300.00**	**767.88**	**230364.00**
	Basic Rate	711.00							
	Area Weightage @ 8%	56.88							
	Total	767.88							

11	13.9.1 Providing and fixing to wall , ceiling and floor high density polythelene pipes 6.00kgs /sqcm working pressure 32mm outside diameter raising mains & exposed distrubition pipes with special flange compression type fitting , wall clips making good the wall , ceiling and floor including cost of all materials labour charges HOM of equipments and testing complete as per specification KSRB 13-8.9 -do- 50mm . Pg no : 91								
			5	**10.00**			**50.00**	**367.20**	**18360.00**
	Basic Rate	340.00							
	Area Weightage @ 8%	27.20							
	Total	367.20							
12	KSRRB 7.7 Providing and fixing in Position in cement concrete 1:3:6 steel glazed widows and ventilaters side hung /top hng fully openable as p[er approved drawings using Z angles of 25X33X3 mm Weighing 1.419kg/m both for outer and inner frames and central mullion section of size 25X46X3mm . weighing 2.28kg/m duly providing Tsection 19X19X3mm weighing 0.839kg/m for glazing of windows not more than 34 cms ctoc including providing and fixing 4mm . thick reeded glass with teakwood beading of required size all steel section should confirm to is 7452:1990, 4nos , of hold facts of approved size section should be cut to length welded and electrically grinded subdividing frames electrically all the steel surface should be throughly cleaned free of rust and painted and finishing wth two coats of ready nix paint of approved colour and make including cost of materials , fixtures , labores , and HOM of machinery Complete as per specification no : KBS :7.12.1 /7.12.2/7.12.3/7.12 . Pg no 32 Item n :7.7							**Sqm**	
			2	**2.50**		**1.50**	**7.50**	**3905.28**	**29290.00**
	Basic Rate	3616.00							
	Area Weightage @ 8%	289.28							
	Total	3905.28							
13	KSRB :9-13-1. .Providing and fixing in position shuters for doors Made out of honey wood styles and railes of 40mm thick with bottom and lock rails 180mm wide top rail and styles 100mm wide as per drawing and panels of 18mm thick of exterior grade melamine impregnated Prelamination particle board of approved colour on both sides including cost of materials , labour , HOM of machineries Complete as per Specification (Excluding Cost of Fixtures) Specification no : Kbs 9.34,9.26.4 Pg no : 53 Item no :9.34							**Sqm**	
			2	**2.20**	**1.20**		**5.28**	**3743.28**	**19765.00**
	Basic Rate	3466.00							
	Area Weightage @ 8%	277.28							
	Total	3743.28							
14	Geophysical survey geophysical investigation of site for sinking Borewell for supplying drinking water to the habitation either through the hand pumps, MWS or PWSS by vertical electrical sounding by adopting venner or schlumbergers's method including recconnaisance suevey of geological formation Geophysical investigation of existing ground Water in the vicinity. its quality , quality & acceptabality of the users indicating the location of the site recommendeddepth of casing pipe required to seal the tope unconsolidated formation including an extra depth 1.0 metre in consolidated formation for aquire proposed to be tapped propable yield and other information required including transportation of instrument and accessories to work site, engating technical personal and labour etc.,PRE- Bangalore Circle-2014-15, Page No-43, Item No-9.4								
	Byatarayanapura SC Burial Ground	Each	1				1.00	1900.00	**1900.00**
14	Sinking of Borewell of 165 mm clear using fast hydraulic rig of capacity 250 PSIG & above 900 CMF & abpve in al strata including over burden upto 22 m fixing of casing pipes, collars and cap with necessary cutting and threading including transporation of rig and surpporting vehicles, screws charges and cost of consumable including yield testing at the final depth with a minimum working of compressor for one hour all as specified.,PRE- Bangalore Circle-2014-15, Page No-43, Item No-9.4								
a	0.00 to 50.00 mtrs	Rmtr	1	50.00			50.00	287.00	**14350.00**
b	50mtr to 100.00 mtr		1	50.00			50.00	379.00	**18950.00**
c	100.00 to 150.00 mtr		1	50.00			50.00	422.00	**21100.00**
d	150.00 to 200.00 mtr		1	50.00			50.00	464.00	**23200.00**
e	200.00 to 250.00 mtr		1	50.00			50.00	513.00	**25650.00**
f	250.00 to 300.00 mtr		1	50.00			50.00	550.00	**27500.00**

16	Supply of ISI Mark 175mm Nominal bore ,plain end steel Casing pipe- grade of steel Fee 410 of wall thickness 5.4 mm thick confirming to IS 1387/1933 and manufactured by basic open hearth electric or basic oxygen process in random lenth of 5 to 7mtrs. Both ends threaded Confirming to IS 554/1985, One end fixed with a Socket Confirming to IS 4270:2001 and the other end with Screwed pipes . All pipes shall be reasonably free from defectes. The tube shall be reasonably straight should be with ISI marking, weighing 25.10kg/mtr. (Inclusive of all taxes) (PRED,2014-15 Page No.II item No-54)								
a	Casing pipe	Rmt	1	40.00			40.00	1325.00	**53000.00**
17	Additional rate on item No. 2 is allowed for drilling in **over burden** and folling casing pipes beyond 20mtrs, rate at 15% and beyond 30mtrs 30% on basic rate of Rs.287 is allowed (PRED,2014-15 Page NoII item No-9.4)								
	a) Above 20 mtrs and Upto 30 mtrs at	Mtrs	1			10.00	10.00	43.05	**431.00**
	b)Above 30 mts		1			10.00	10.00	86.10	**861.00**
18	Providing 175 mm dia **MS Collar** (RDED SR page ii, item55)								
		Each	11X1				11.00	150.00	**1650.00**
19	Providing 175 mm dia **MS Cap**(as per RDED SR page ii, item-54)								
		Each	1				1.00	100.00	**100.00**
20	Supply and delivery at site brand new Texmo / Innoval / Lubi / Sabar / Atalanta / Calamal / waterman / Radha make suitable vertical installation in 150mm dia. Borewells comprising of single stage or miultistage CF pump close coupled by means of stainless steel coupling to suitable HP suitable speed totally enclosed and filled with pure drinking water (Wet type) squirrel cage **submersible induction mortor** suitable for operation of 3Ph., 50Hz. 380/44 volts AC supply fitted with required accessories such as suction. casing, suction strainers, sand guard Non return valve etc., complete the pump and motor shall form an integral unit with all the required fittings 15HP 30 stage SE Approved Rate Letter No:2133								
	Byatarayanapura SC Burial Ground	No	1				1.00	52000.00	**52000.00**
21	Supplying and Drawing 3 core Flat PVC Shalted Submersible Pump Cable Manufactured with Electrolytic Grade Copper with Flexible copper conductor to table 3 class 5 of IS 8130-1984 and Virgen PVC insulation and Sheeated Suitable for working Voltage Upto 1100 Volts as per Page No:49 item No 29C/1 PREE- SR 2014-15								
	Byatarayanapura SC Burial Ground	Mtrs	1	296.00			296.00	151.00	**44696.00**
22	Supplying and fixing 50mm Non Return Vavle of vertical type of approved make including cost of all materials labour HOM of equipment with all leads Complete as per Specifcation (As Per Rate approved By SE, RDED, Letter No.2081/2014-15								
	Byatarayanapura SC Burial Ground	Nos	1				1.00	1530.00	**1530.00**
23	Supplying and fixing 50mm GM GaTe Vavle (As Per Rate approved by SE, RDED, Letter No.2081/2010-11 Dt: 28-07-2010)								
	Byatarayanapura SC Burial Ground	Nos	1				1.00	1430.00	**1430.00**
24	Supplying and fixing 160mm Borewell cap with clampset (As Per Rate approved by SE, RDED, Letter No.2081/2014-15								
	Byatarayanapura SC Burial Ground	Nos	1				1.00	690.00	**690.00**
25	Supplying and fixing 50mm GI Union (As Per Rate approved by SE, RDED, Letter No.2081/2014-15								
	Byatarayanapura SC Burial Ground	Nos	1				1.00	245.00	**245.00**
26	Supplying and fixing 50mm GI Elbow (As Per Rate approved by SE, RDED, Letter No.2081/2014-15								
	Byatarayanapura SC Burial Ground	Nos	1x2				2.00	120.00	**240.00**
27	Supplying and fixing 50mm GI coller Heavy duty								
	Byatarayanapura SC Burial Ground	Nos	35				35.00	1350.00	**47250.00**
28	Supplying and delivery at site brand new star / Essen / Lotus / Sun shines / Adharsh / GK Controls best indigenous make combined energy meter cum control panel board unit of size 1200x600x350mm minimum mechanically strong vermin and water proof. The unit shall have two detachable doors suitable for opration on 3ph, 50 hz, 380/440 volts, AC supply with spring loaded latch, locking device with a key ribs should be provided inside the door canopy apron and louvers ventilators shall be provided the combined energy meter cum control panel board unit suitable for operation on 3ph, 50 hz, 380/440 volts AC supply shall be consists etc., complete the panel board shall be consist etc., complete the panel board shall be fabricated on single unit in the above componenets panel board for suitable pumpset with star delta staretr out door type 10hp to 15 hp (As per rate approved by SE, RDED, Letter No-2133/2014-15								

	Byatarayanapura SC Burial Ground	Nos	1				1.00	10000.00	**10000.00**
29	Providing and fixing of 50mm G.I pipe 'C' class heavy duty foe erection of submersible pumpset (As per BWSSB Store Issued Rate)								
	Byatarayanapura SC Burial Ground	Mtrs	35	6.00			210.00	402.75	**84578.00**
30	Erection of combined panel board and meter unit with necessary materials and labour including providing cement concrete foundation bed cont door type etc., complete (As Per Rtae Approved by CE, RDED, Letter No-8650/2003-01								
	Byatarayanapura SC Burial Ground	Nos	1				1.00	475.00	**475.00**
31	Supplying of TPST with rewireable porcelain channels in SM encloser 15/32 amps P-346, i-1.I(a), BWSSB SR 2008-09.								
	Byatarayanapura SC Burial Ground	Nos	1				1.00	1350.00	**1350.00**
32	Supplying and fixing 500x500x65mm polished wood board made up not less than 15mm thick plank in front plank one end provided for olding at other end fixing the same of the valve using through bolts and nuts, P-346, I-2(f), BWSSB SR 014-15								
	Byatarayanapura SC Burial Ground	Nos	1				1.00	275.00	**275.00**
33	Supplying and fixing LED Type panel board indicating lamp with required colour suitable for 220 v AC 50Hz 12/24 V DC Group 'B'. P-354, I-35(b), BWSSB SR 2014-15								
	Byatarayanapura SC Burial Ground	Nos	1	3.00			3.00	350.00	**1050.00**
34	Supplying and drawing each PVC insulated 650/100 V grade wire in the conduct (Open or Concealed system of wiring) 7/20 or 7/36 copper wire. P-332, I-20, ii(d), BWSSB SR 2014-15.								
	Byatarayanapura SC Burial Ground	Nos	1	20.00			20.00	25.00	**500.00**
35	Supplying, fixing and wiring heavy duty low voltage capacitors confirming to I 2834, 3 PHASE 400/440 Volts grade for power factor improvement of rotating machinery capacitor in KVAR - rating Nos 2 KVAR Capacity P-354, I-34(a), BWSSB SR 2014-15								
	Byatarayanapura SC Burial Ground	Nos	1				1.00	350.00	**350.00**
36	Supplying and fixing miniature Circuit breakers on existing MCB distribution boards using necessary fixing materials and wiring complete as required P-350, I-13 (E, a), BWSSB SR 2014-15.								
	Byatarayanapura SC Burial Ground	Nos	1				1.00	1075.00	**1075.00**
37	Supplying, fixing, wiring earth electrode for grounding conduits, LC cutouts and other equipments on the meter board using 40mm dia 2.90mm thick GI pipe 2.50m long buried in a pit. The pit should be filled with equal proportion of solt and charcoal 150mm alround the pipe to complete depth. the connection from the pipe to the conduct etc., is to be established through GI wire of size as per ISI specifications 7.3.3 IS 732 using 12mm dia bolts, nuts, washers and check nuts etc., the pipe shall have 16 throught holes of 122mm dia P-377, I-7, BWSSB SR 2014-15								
	Byatarayanapura SC Burial Ground	Nos	1				1.00	1500.00	**1500.00**
38	Supplying and fixing class A (medium duty) GI pipe wall thickness not less than 3.25mm on pole.								
	Byatarayanapura SC Burial Ground	Nos	1	10.00			10.00	220.00	**2200.00**
39	Supply 1.1 KV class UG cable from nearest BESCOM pole to panel board including earth work and road restoratio 4 core 16 sqmm. P-378, I-10(d), BWSSB SR 2014-15								
	Byatarayanapura SC Burial Ground	Mtrs	1	35.00			35.00	150.00	**5250.00**
40	Labour charges for laying 1.1 KV class UG cable when supplied by agencies in existing trenches GI pipe / stoneware pipe/ on pole as required, P-379, I-77 (a), BWSSB SR 2014-15.								
	Byatarayanapura SC Burial Ground	Mtrs	1	35.00			35.00	5.00	**175.00**
41	Digging of trench of 0.6m deep x 0.5m wide refilling the trench to the required level and consolidating etc., complete P-379, I-12 (b), BWSSB SR 2014-15								
	Byatarayanapura SC Burial Ground	Mtrs	1	30.00			30.00	50.00	**1500.00**
42	Supply and fixing LT cast iron pot heads suitable for 1.1 KV class UG cable filled with neccesary bitumen / insulating compound complete with termiinalas, clamps, bolts, nuts, washers etc., P-380, I-16(b), BWSSB SR 2014-15								
	Byatarayanapura SC Burial Ground	Nos	1				1.00	240.00	**240.00**
43	Supplying and fixing of porcelain fuse channel with cut-out on existing / new wooden panel using neccesary nuts, bolts and washers etc., complete P-32, I-3 (b), PWD ELECTRICAL SR 2014-15								
	Byatarayanapura SC Burial Ground	Nos	1	6.00			6.00	219.00	**1314.00**
44	BESCOM Deposit charge and miscellanious.	L.S	1				1.00	14000.00	**14000.00**
45	Cutting of road surface for pipeline trenches and disposing of the excavated stuff as directed including barricading, danger lighting etc., in the Asphalt surface road. (Pg. No-267, I.No-37.38)								
	Byatarayanapura SC Burial Ground	Cum	1	50.00	0.30	0.15	0.15	237.44	**36.00**

46	Cutting of road surface for pipeline trenches and disposing of the excavated stuff as directed including barricading, danger lighting etc., in the Cement concrete road. (Pg. No-267, I.No-37.40)								
	Byatarayanapura SC Burial Ground	Cum	1	50.00	0.30	0.15	2.25	497.14	**1119.00**
47	Earthwork excavation for foundation of buildings water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications. specification. Noll KBS 2.1.C/2.9.4/2.18/2.19 (Pg. No-5, I.No2.4)								
	Byatarayanapura SC Burial Ground	Cum	1	50.00	0.30	0.30	4.50		
							4.50	198.22	**892.00**
48	Providing and installing at site of work P.V.C pipees including cost of pipes and specials and labour including lowering into trenches, laying true to line, level and perfect linking at joints leak proof including jointing of approved type with all labour and lift charges, handling charges including encasing the pipe alround to a depth not leass than 15 cms with gravel or selected earth available from the excavation etc., complete PVC pipes of 6kg/Sqm 75mm Dia.(Page NO-14, iTEM no-3.4.2 (b), of PRE SR 2014-15).								
	Byatarayanapura SC Burial Ground	Rmt	1	70.00			70.00	117.00	**8190.00**
49	Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m and lift upto 1.5m, including cost of all labour complete as per specification. (Pg. No-6, I.No-2.11)								
		Cum		Same As Item No - 34			4.50	53.00	**239.00**
50	Disposing of excavated earth to the final place of disposal with all lead and lift and as directed by the Engineer in charge of the work. (Lead up to 15.00 KM)								
		Cum		Same as Item No- 32 & 33			2.40	106.85	**256.00**
51	Transportation of pumping machineries PRE SR 2014-15 PG 51/10.3.19						2.00	850.00	**1700.00**
52	Erection of Pumping machineries PRE SR 2011-12 PG 51/10.3.20						1.00	850.00	**850.00**
53	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. (P. 19, I.No. 4.46) SR 2014-15								
			24.00	60.00			1440.00		
							1.40	78351.84	
	Basic Rate	72548.00							
	Area Weightage @ 8%	5803.84							
	Total	**78351.84**							
54	Provision For Gate	L/S	3						100000.00
	Total								**1478842.00**
55	Third Party inspection 1%								**14788.00**
56	Miscellaneous & Unforeseen Charges								**6370.00**
									1500000.00

Grand Total

Fifteen Lakhs only

Technical Sanction for Rs. 15-00 L
Fifteen lakhs only
To Cost
63 12/02/15
377 12/02/15
12/02
AEE/JE
EE (RTP.Div.)

CERTIFICATE

1. Certified that I have personally inspected the area and prepared the estimate.
2. Certified that the work proposed in this estimate is not including in any other scheme.
3. Certified that the estimate is prepared as per 2014-15 MI SR Bangalore circle.
4. This works is not split up.

Junior Engineer

Assistant Executive Engineer
Kodigehalli Sub Division

Executive Engineer
Byatarayanapura Division
9/2/2015

Sanction for Rs.....

Administrative Approval

Accorded for Rs 15.00 lakh Rs

is accorded under head.....

P-1878

.....

registered as CE No. 172 Dt: 12.02.15 Subject

to Conditions contained

No.....

AE/JE TA SE (BTP) CE (BTP)